



9-(NOT IN CONTRACT)

8-(NOT IN CONTRACT)

CONSTRUCTED SITES 2002
REMAINING DESIGNED SITES

GENERAL NOTES

- EXISTING GRADES, STORM SEWER AND EDGE OF PAVEMENT AS SURVEYED BY KILLAM ASSOCIATES.
- ALL CURB-MOUNTED CATCH BASINS SHALL BE PROVIDED WITH SIX (6) FEET OF CONCRETE CURB ON EITHER SIDE OF THE INLET.
- ALL NEW CASTINGS SHALL BE FITTED WITH BICYCLE TYPE GRATES.
- THE CONTRACTOR SHALL REUSE EXISTING CASTINGS, AS SHOWN ON PLANS. ALL UNUSED CASTINGS SHALL BE RETURNED TO THE DEPARTMENT OF PUBLIC WORKS YARD AT 30 LYCOSKY DRIVE, WEST MILFORD, NEW JERSEY.
- THE CONTRACTOR SHALL INSURE THAT ADEQUATE TRAFFIC CONTROL DIRECTORS AND DEVICES REQUIRED SHALL BE PROVIDED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE TOWNSHIP AND SHALL BE INCLUDED IN THE VARIOUS PRICES BID UNDER THIS CONTRACT.
- THE CONTRACTOR SHALL NOTIFY HOME OWNERS TWO (2) DAYS PRIOR TO THE START OF CONSTRUCTION AND SHALL MAINTAIN ACCESSIBILITY TO THE HOMES AT ALL TIMES.
- THE CONTRACTOR SHALL RESTORE ALL IMPROVEMENTS DISRUPTED DURING CONSTRUCTION.
- LOCATION OF ALL EXISTING UTILITIES IS APPROXIMATE. BEFORE ANY EXCAVATION IS TO BEGIN, ALL UNDERGROUND UTILITIES ARE TO BE VERIFIED AS TO THEIR LOCATION, SIZE AND TYPE BY THE CONTRACTOR AND THE APPROPRIATE UTILITY COMPANY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING WITH THE APPROPRIATE UTILITY COMPANY FOR ALL ACCESSORY RELOCATIONS.

TOWNSHIP OF WEST MILFORD PASSAIC COUNTY, NEW JERSEY GREENWOOD LAKE PHASE II IMPLEMENTATION PROJECT SITE LOCATIONS	
JANIS G. COE Municipal Engineer <i>(Signature)</i>	Date: 4/20/02 Scale: AS SHOWN Project No: 02-04 Drawing No: 02-04
KILLAM ASSOCIATES 27 HARRISON DRIVE, SUITE 2024 WEST MILFORD, NEW JERSEY 07088	
SHEET NO. 1 OF 1	DATE: 4/20/02